


ABBREVIATIONS:			
A.T.	ACOUSTIC CEILING TILE (600x1200)	H.R.	HIGH RIDGE
A.F.F.	ABOVE FINISH FLOOR	I.T.D.	INTERIOR DESIGN SPECS
ALUM.	ALUMINUM	MIR	MIRROR
B.F.	BARBER FREE	M/M	MARBLE/MARBLE FINISH
B.H.	BULKHEAD	ND	NO DRAIN
BLDG.	BUILDING	N.I.C.	NOT IN CONTRACT
C.H.	CEILING HEIGHT	PC	PRE-CAST CONCRETE
C.T.	CEILING TILE (STANDARD 600x600)	P.E.V.S.	PAINT EXPOSED STRUCTURE
CARP	CARPET	P.L.W.D.	PLYWOOD
CBK	CONC. BLOCK	P.M.	PAINTED MASONRY
CBY/T	CERAMIC TILE	P.M.C.	PORCELAIN TILE
CONC.	CONCRETE (C/A SEALER)	P.M.T.	PORCELAIN MOSAIC TILE
CONC.S	CONCRETE (C/A SEALER)	P.R.C.-F.N.	PRE-FINISHED
CONT	CONTINUOUS	P.R.	PAINT SURFACE
DBL	DOUBLE	P.R.P.	RETRACTABLE WALL PANEL
EL.	ELEVATION	R.T.U.	ROOF TOP UNIT
EXP.	EXPOSED	S.D.	SOAP DISPENSER
EXP.S	EXPOSED STRUCTURE	S.F.L.	SAFETY FLOORING
F.F.	FINISH FLOOR	SIN	SINGLE
F.S.PRAY	FIRE-PROOF SPRAY	SPEC	SPECIFICATIONS
G.C.	GENERAL CONTRACTOR	STD.C.	STANDARD PAINT COLOUR (TO BE CONFIRMED)
GL	GLASS	TP	TOILET PAPER DISPENSER
GWB	GEORGIAN WALLBOARD	TP.	TYPICAL
GMG	GEORGIAN WIRE GLASS		
H.M.	HOLLOW METAL		

### 5 ABBREVIATIONS

SYMBOLS		EXISTING SPOT ELEVATION	
ROOM NUMBER	1008	SPOT ELEVATION	+100.000



### DRAWING SYMBOLS LEGEND



GENERAL NOTES:			
1.	ALL FIRE SEPARATIONS ARE CONTINUOUS, MAINTAIN INTEGRITY OF AND AROUND THE PERIPHERY OF THE ASSEMBLY. REFER ALSO TO A200 SERIES DRAWINGS.		
2.	CORRESPONDING LOCATIONS AND EXTENT OF LOAD BEARING SHEAR WALLS WITH STRUCTURAL DOCUMENTS		
3.	SUBSTITUTE "BERSHIELD" OR CEMENT BOARD IN LIEU OF GYPSUM BOARD WHERE SPECIFIED. THE TILE GROUT, REFER TO AND CORRESPONDING ALL WORK WITH ROOM FINISH AND COLOR SCHEDULES.		
4.	A PARTITION TYPE WITH A SUFFIX 'S' DENOTES A PARTITION WITH ACOUSTIC BATT INSULATION FOR FULL HEIGHT AND EXTENT OF PARTITION (SEE REMARKS COLUMN).		
5.	ALL STRUCTURAL AND ACOUSTICAL PARTITIONS TO EXTEND TO UNDERSIDE OF RATED CEILING ABOVE.		
6.	ABUSE-RESISTANT GYPSUM BOARD MAY BE USED FOR RESISTANCE TO IMPACT AND DAMAGE TO FINISH SURFACES. SEE ROOM FINISH SCHEDULE FOR LOCATIONS REQUIRED.		
7.	1/2" GYPSUM BOARD MAY BE SUBSTITUTED FOR 5/8" GYPSUM BOARD WHERE SPECIFIED FOR ACOUSTICAL PARTITIONS WITHIN DESIGNATED UNIT AREAS. (NOT APPLICABLE @ FIRE-RATED ASSEMBLIES)		

ASSEMBLY TYPES SCHEDULE			
ASSEMBLY / PARTITION TYPE	FIRE RATING & TEST NO.	STC RATING & TEST NO.	REMARKS

INTERIOR WALLS			
P2 / P2S	N/A	"P2S"-STICB (OBC-SG8 WOI #344 Sim.)	-FILL STUD CAVITY W/ SOUND ASSEMBLY FOR P2S -OP. BOARD ONE SIDE @ WALL CAVITIES (E. WASHROOMS)
P3 / P3S	N/A	"P3S"-STIC41+ (OBC-SG8 WOI #576 Sim.)	-FILL STUD CAVITY W/ SOUND ABSORB. BATT FOR "P3S" ASSEMBLIES
P3F60	N/A	60minutes (ULC Design#407)	PROVIDE BATT INSUL ALONG WALLS @ CORNER/LOADING/ETC & PROVIDE BATT INSUL W/ SOUND ABSORB. BATT FOR "P3S" WALL ASSEMBLY
F1	N/A	N/A	WALL FURRING WITH BATT BATT INSUL.

EXTERIOR WALLS			
P1	N/A	N/A	1/2" GYPSUM BOARD, VAPOUR/AIR BARRIER, METAL STUDS @ 16" O.C., TILED W/ BATT INSUL.
P4	N/A	N/A	-PRECAST CONC. WALL PANELS
P5	N/A	N/A	-9" PRECAST "SANDWICH" WALL PANELS (E-F RIGID INSUL AS PER MANUF. SPECS)
P6	N/A	N/A	10" CONC. BLOCK TO U/A OF METAL STUDS @ 16" O.C. STEEL COLUMN (SEE STRUCT'L DWGS.)

STRUCTURAL COLUMN WRAPS			
CW120	120 Minute (Per Spray-Foam Manuf. Specs)	N/A	-SELF-ADHERING FIRE-RETARDANT SPRAY-FOAM COVERING
ROOF ASSEMBLY			
RF1	N/A	N/A	-GRAVEL BALLAST / BUILT-UP ROOFING MEMBRANE STRIPATE -1/4" (Min. R20) RIGID INSUL., V.B -1/2" STEEL DECK & DWGS (SEE STRUCT'L)

### GENERAL NOTES:


- WHERE ELECTRICAL AND MECHANICAL FITMENTS OCCUR ON EXISTING CEILING OR WALLS, FITMENTS SHALL BE INSTALLED IN THE EXISTING CEILING OR WALLS. OTHERWISE, ALL MECHANICAL AND ELECTRICAL FITMENTS AND SERVICES SHALL BE BUILT INTO WALLS.
- MATERIAL AND FINISH FOR ALL COLUMNS SHALL BE SAME AS WALLS IN WHICH THEY OCCUR OR, IF FREESTANDING, SAME AS REMAINDER OF ROOM, UNLESS NOTED OTHERWISE.
- GYPSUM BOARD APPLIED TO CONCRETE MASONRY UNITS OR POURED CONCRETE SHALL BE INSTALLED ON METAL FURRING UNLESS SPECIFIED OTHERWISE.
- ALL DIMENSIONS, NOTED AS "A" ARE TO BE SITE VERIFIED AND VERIFIED BY THE CONTRACTOR PRIOR TO ANY CONSTRUCTION. THE CONTRACTOR TO ADVISE THE ARCHITECT (IN ADVANCE) IN WRITING OF DEVIATIONS (SITE CONDITIONS) FROM EXISTING BASE BUILDING DRAWING INFORMATION PROVIDED TO DESIGNER BY BUILDING OWNER. ADVISE DESIGNER FOR COORDINATION OF WORK.
- DIMENSIONS TO INTERIOR PARTITIONS ARE TO FACE OF GYPSUM BOARD, FACE OF CONCRETE MASONRY UNIT OR FACE OF POURED CONCRETE UNLESS NOTED OTHERWISE.
- WALL PARTITIONS ARE INDICATED WITH A "P" FOLLOWED BY A NUMBER. SEE PARTITION TYPES FOR PARTITION COMPONENTS.
- ALL EXTERIOR EXPOSED STEEL TO BE HOT DIPPED GALVANIZED. THIS INCLUDES BOTH STRUCTURAL AND MISCELLANEOUS STEEL.
- ALL CONSTRUCTION SHALL CONFORM TO THE LATEST PRINTING OF ONTARIO BUILDING CODE.
- ALL FITMENTS (IE. DOORS, WINDOWS, SCREENS, CASEWORK, ETC.) SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS SPECIFICATIONS AND STANDARDS.
- ONLY THE SHOP DRAWINGS REQUESTED IN THE SPECIFICATION, WILL BE REVIEWED.
- ALL FIRE RATED PARTITIONS ARE TO EXTEND TO U/S OF STRUCTURE
- REFER TO SECTION AND DETAILS FOR EXTERIOR WALL SYSTEM MATERIALS.

### GENERAL NOTES

ARCHITECTURAL	
A001	TILE SHEET
A001	SYMBOLS, LEGENDS, MISC. DETAILS & ASSEMBLY TYPES
A100	SITE PLAN
A200	CODE ANALYSIS, BARRIER-FREE DESIGN, MATRIX
A201	FIRE SEPARATIONS
A301	OVERALL GROUND FLOOR
A302	MEZZANINE & ROOF PLAN
A303	PARTIAL GROUND PLAN BLOW-UP
A304	PARTIAL GROUND PLAN BLOW-UP
A320	REFLECTED CEILING PLAN
A400	EXTERIOR ELEVATIONS
A500	CROSS SECTIONS
A501	WALL SECTIONS
A502	WALL SECTIONS & DETAILS
A503	ROOF ACCESS LADDER DETAILS
A504	DOOR & WINDOW SCHEDULES
A600	
A700	INTERIOR WALL ELEVATIONS

### ARCHITECTURAL DRAWING LIST

REV.	DATE	DESCRIPTION
1	APR/10	ISSUED FOR REVIEW
2		ISSUED FOR TENDER
3		
4		
5		
6		
7		
8		
9		
10		



**FABIANI ARCHITECT LTD.**

ARCHITECTS

REGISTERED PROFESSIONAL ARCHITECTS

ONTARIO ASSOCIATION OF ARCHITECTS

**ATTRIDGE TRANSPORT NEW OFFICES**

PROJECT NAME:

DRAWING NAME: **SYMBOLS, LEGENDS, MISC. DETAILS & ASSEMBLY TYPES**

PROJECT NO.: **09004**

DATE: APR. 10

SCALE: AS NOTED

**09004**

PROJECT NO.

DATE: APR. 10

SCALE: AS NOTED

PROJECT NAME: **ATTRIDGE TRANSPORT NEW OFFICES**

DRAWING NAME: **SYMBOLS, LEGENDS, MISC. DETAILS & ASSEMBLY TYPES**

PROJECT NUMBER: **A001**